

# **NERC GMD Reliability** Standards

Frank Koza, PJM, Chair of NERC GMD Standard Drafting Team Space Weather Workshop 2015, Boulder, CO April 16, 2015












## **Potential Impacts on the Power System**





### **EOP-010-1** – **GMD** Operations

- Requires Reliability Coordinators (RC) to develop Operating Plans to coordinate GMD Operating Procedures in their area
- Requires Transmission Operators (TOP) to develop GMD Operating Procedures that include:
  - Steps to receive space weather information
  - System Operator actions based on predetermined conditions
- Applies to RCs and TOPs with grounded wye transformers >200 kV on the high side
- U.S. enforcement date April 1, 2015




## Typical Operational Mitigation Actions

- Ahead of the storm (1-3 days)
  - Raise situational awareness
  - Posture the system—e.g. return or stop outages
- Day of storm (hours ahead or imminent)
  - Monitor GIC detectors/magnetometers/reactive reserves
  - Add generation and reactive resources
- Real Time
  - Redispatch generation, based on pre-study
  - Selectively, remove lines and transformers from service, based on prestudy
  - Boost voltage schedules on generation, where necessary




#### **PJM GIC Detectors**










**Transformer Neutral Amps** 



### **Point Beach 2 GSU Transformer**



Two Rivers, Wisconsin (~44 degrees<sup>o</sup> N)


### **TPL-007 Deliverables**



- Requires a <u>GMD Vulnerability Assessment</u> of the system for its ability to withstand a Benchmark GMD Event without causing a wide area blackout, voltage collapse, or damage to transformers, once every 5 years.
  - Applicability: Planning Coordinators (PCs), Transmission Planners (TPs)
- Requires a <u>Transformer thermal impact assessment</u> to ensure that all high-side, wye grounded transformers connected at 200kV or higher will not overheat based on the Benchmark GMD Event
  - Applicability: Generator Owners (GOs), Transmission Owners (TOs)



### **GMD Assessment Process Overview**





# Perform GMD Vulnerability Assessment—Step 1

Calculate GICs and increases in reactive power consumption


$$E_{peak} = E_{benchmark} \times \alpha \times \beta$$
 (in V/km)

$$\begin{array}{ll} E_{\text{peak}} = & \text{Benchmark geoelectric field magnitude at System location} \\ E_{\text{benchmark}} = & 8 \text{ V/km} \\ \alpha = & \text{Factor adjustment for geomagnetic latitude} \\ \beta = & \text{Factor adjustment for regional Earth conductivity} \\ & \text{model} \end{array}$$

Major power flow analysis programs (PSS/E, PSLF, and PowerWorld) have GIC calculation modules



### **Reference Geoelectric Field Amplitude**




Statistical occurrence of spatially averaged high-latitude geoelectric field amplitudes from IMAGE magnetometer data (1993 – 2013)




# Perform GMD Vulnerability Assessment—Step 2

- Add reactive power losses due to GIC into the AC power flow
  - Consider impact of harmonic currents
  - Solve AC power flow case
  - Did the system collapse or go into cascading? Not a trivial problem –
     planners are used to looking for individual equipment limit violations
  - If the system is able to withstand the Benchmark GMD event, then the assessment is complete.
  - If the system cannot withstand the Benchmark GMD event, go to R7



# PJM Preliminary Vulnerability Assessment

#### Voltage Performance, Spring Light Load






## **Transformer Thermal Impact Assessment**


#### Asset owners:

- Obtain GIC peak value and time series
- If the calculated GIC for the transformer is less than 75 amps,
   then no further assessment is required
- If the calculated GIC for the transformer is more than 75 amps,
   a more detailed analysis should be done













### **Transformer Thermal Assessment**

- Consult manufacturer or IEEE Std C57.91 for temperature limits
- Assessment approaches:



Transformer manufacturer capability curves



Thermal response simulation



# PJM Preliminary Thermal Assessment Results

 Transformers with the highest GICs (divide by 3 phases; peak electric field in PJM is ~3V/km)

Transformer Description	Area	Current, pu (3	Avg Neutral Amps (3 phase)
765/26 #2	AEP	1.147	
765/26 #1	AEP	1.059	79.952
500/22 #1	PJM	0.645	74.491
765/345 #1	AEP	0.919	69.322
<mark>765/138 #2</mark>	AEP	0.883	66.610
765/500 #1	AEP	0.870	65.680
500/22 #1	DVP	0.565	65.260
345/25 #5	CE	0.388	64.975
500/25 #1	PJM	0.554	63.982
500/22 #1	PJM	0.554	63.982
500/230 #1	DVP	0.539	62.256
500/22 #1	PJM	0.539	62.219
345/138/34.5 # 1	CE	0.369	61.810
765/345/33 #1	CE	0.726	54.762
345/22 #8	DEO&K	0.320	53.517
500/230 #2	DVP	0.443	51.158
500/230 #1	DVP	0.442	51.062
765/345 #3	AEP	0.651	49.102
345/34.5 #1	AEP	0.283	47.431



## **Revised Implementation Plan**

A number of entities expressed concerns with the proposed implementation plan so it was revised as follows:

18 Months48 Months•R2•R6Date of Approval•System Assessment













#### **6 Months**

- •R1
- •Identify Responsibilities

#### 24 Months

- •R5
- •GIC Flow Information

#### **60 Months**

- •R3, R4, and R7
- •GMD Assessment
- •Corrective Action Plan